

PROCESS FOR IN-BUILDING PS DAS DEPLOYMENTS

(START)



Identify AHJ & Frequency License Holder

- □ Determine AHJ requirements□ Obtain rebroadcast agreement(s)
- ☐ Determine applicable standards (NFPA72, NFPA 1221, IFC, ICC, FCC, etc.)



Site Survey & Baseline Testing

- ☐ Initial survey of floor plans, equipment locations, and impairments
- □ Determine downlink coverage DAQ 3.0*



Preliminary Design

- ☐ RF link budgets☐ Initial antenna and cable layouts
- ☐ Bill of materials (BoM)



Statement of Work

☐ Ensure that all project requirements are clearly defined.



RF SURVEY

RF Survey & CW Testing

☐ Perform interference and propagation measurements



Update Design

☐ Revise preliminary design & BoM based on results



Pre-Construction Survey

☐ Installer walk-thru to validate cable routes and equipment locations



Final Design

□ Revise based on changes to installation design if necessary



Order Equipment

□ Place your order for equipment.



Installation

☐ Install cables, antennas, and active equipment.



Commissioning

- ☐ Verify RF & optical cable performance (if applicable)
- $\hfill\Box$ Set system gains
- ☐ Test system



System Acceptance

- Post install walk through with AHJ Fire Marshal to demonstrate compliance.
- ☐ Customer obtains Certificate of Occupancy from AHJ

(END)

*Delivered Audio Quality (DAQ) The DAQ scale includes a scale ranging from 1 to 5, with 1 being unusable audio output and 5 being perfect.			
DAQ 1:	Unusable. Speech present, but not understandable.	DAQ 3.4:	Speech understandable without repetition. Some noise or distortion present.
DAQ 2:	Speech understandable with considerable effort. Requires frequent repetition due to noise or distortion.	DAQ 4:	Speech easily understandable. Little noise or distortion.
DAQ 3:	Speech or understandable with slight effort. Requires occasional repetition due to noise or distortion.	DAQ 5:	Perfect. No distortion or noise discernible.

